302

Notification dated 2nd February 1904.

No. *i.* DRAINAGE AREA.

It is hereby notified, in accordance with Section 16 (1) Regulation No. III of 1903 for the improvements of the City of Mysore, that a scheme for the improvement of that portion of the City described as No. i drainage area has been prepared. The area comprised lies to the north of Bakshi Budankhan's street and Gowligar street and extends to the existing limits of the town on the north. It is bounded on the west by the new Idga road and on the east by the Jalpuri Extension and the road in continuation of Hale Nazarbad road which meets the travellers' bungalow road. The area is divided into drainage blocks bearing Nos. 16, 17, 18, 19, 20, 21, 29 and 30 as indicated on plans.

The particulars of the scheme, a map of the area, and statements specifying the lands and properties to be acquired may be seen at the Chairman's Office, now held in the building known as Lacey's Court, between 11 A. M. and 5 P. M., on office days.

2. The proposed improvements may be summarized under the following heads :—

(1) the opening out of roads, lanes and open spaces with a view to relieve congestion, facilitate drainage and conservancy and to admit sufficient light and air.

(2) the demolition of insanitary houses and conserving of open spaces.

(3) the construction of drains.

(4) the construction of latrines and the provision of other public conveniences.

3. The details of widening the existing lanes and opening out new roads and conservancy lanes in the several drainage blocks are noted below :—

Block No. 16.—Five cross roads, running from east to west, are proposed to be taken off from new Idga road and also five from north to south, in all ten.

Block No. 17.—(1) A new broad road is proposed to be opened from Kalasagere road due east, to join Kaliaman temple street.

(2) A new 30-feet road is also proposed parallel to the above and to the north of it and two minor parallel roads to the previous ones.

(3) Another new road is intended from Idga Extension to meet rampart wall road.

In all 30 roads will be handled in this block.

Block No. 18.—In this block 19 roads and lanes will be dealt with, none of much importance, and mostly intended to remove congestion and facilitate conservancy.

Block No. 19.—Total number of roads handled will be 14 and none of much importance.

Block No. 20.—Total number undertaken will be 17 and the most important of these are, the straightening of the Earangare-Holagere street and opening two new roads Nos. 10 and 11 running east to west to remove congestion.

Block Nos. 21 and 22.—Are in one sheet. Total number of roads to be dealt with will be 12, of these the most important is a new parallel road between Church street and Holagere street.

Block Nos. 29 and 30.—In one sheet. Nine roads will be dealt with for conservancy purposes.

D. SITARAM RAO,
Chairman of the Board of Trustees, Mysore.

Notice dated Madras, 25th January 1904.

1. A class for the training of Temporary Sanitary Inspectors for plague duty will assemble at the King Institute of Preventive Medicine at Guindy at 9 A.M., on Monday the 8th February 1904. Applications accompanied by copies of testimonials are invited from candidates who have passed the Matriculation, the Middle School Examination in the 1st Class or any other Examination which qualifies for the Public Service. Candidates who pass the final examination and are sent on Plague duty will be allowed half pay in accordance with their position on the passed list for the training period. Applications should be addressed to the undersigned.

2. Admission to the class will be subject to approval of testimonials and general fitness for duty by the undersigned.

J. S. C. BARTLEY, L.R.C.P. & S.E.,
Personal Assistant to the Sanitary Commissioner for Madras.

CHITALDRUG DIVISION.

Notice dated 27th January 1904.

Notice is hereby given that a sum of Rs. 10-12-1 being the arrears due to Tasle Worker Venkata Rao of annual repairs of Salem-Bellary road is outstanding in the accounts of Executive Engineer's Office, Chitaldrug Division, and if the said contractor or his legal representative do not appear and receive the amount from this office within three months' time from this date the amount will be credited to Government.

Y. SRINIVASA RAO, *Executive Engineer.*

TUMKUR DIVISION.

The 6th February 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 1st March 1904, for restoring Bugadanhalli tank, Registered No. 304, Tumkur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1904.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Bugadanhalli tank, Registered No. 304, Tumkur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Restoring Bugadanhalli tank Registered No. 304, Tumkur Taluk.

Items of work.	*Per*	*Quantity.*
Bund—		
Earthwork	C. yd.	12,097
New stone work	,,	2,318
Old stone work with new jelly	,,	2,271
Turfing	S. yd.	14,345
Grade stones, new	Each.	42
Index stones	do.	42
Register No. stone	do	1
B. M. stones	do	2
No. I Left waste weir 33 ft. long—		
Dismantling the present body wall, etc.	L. S. Rs.	
Burnt brick in chunam	C. ft.	349
Plastering with chunam	Sqr.	2·8[illegible]
Burnt stone in chunam	C. ft.	77
Burnt stone slabs	S. ft.	7[illegible]
Concrete	C.f t.	[illegible]
Earthwork and turfing to wing bunds	L. S. Rs.	
Re-setting apron	Do	
No. II Left waste weir 215 ft. long—		
Dismantling the present body wall, etc.	L. S. Rs.	
Burnt brick in chunam	C. ft.	99
Chunam plastering	Sqr.	·19
Burnt stone in chunam	C. ft.	1276
Burnt stone slabs	S. ft.	756
Concrete	C. ft.	326
Earthwork and turfing to wing bunds	L. S. R.	
Re-setting apron	Dc	
No. III Right waste weir 166 ft. long—		
Excavating foundation and forming wing bund including turfing ...	L. S. Rs.	
Burnt brick in chunam	C. ft.	1,080
Burnt stone slabs	S. ft.	270
Plastering	Sqr.	3·03
Rough stone apron	C. yd.	74

C. MADHAVA ROW, *Offg. Executive Engineer.*

MARIKANAVE WORKS.

Dated 25th January 1904.

Wanted immediately three temporary Clerks on Rs. 20 + 4 for Marikanave channels. None but Matriculates to apply.

C. T. DALAL, *Superintending Engineer.*